BRUHAT BANGALORE MAHANAGAR PALIKE

Project Division, Yelahanka Zone

Modified SCHEDULE - B

Development and Improvements of Road, Drain and Covering Slabs at Agrahara Layout in Ward No.05

SNo	Quantity	Item Name	Unit	In figures	In words
1	1336.50	Removing & Refixing stone slabs of drains and pointing in C.M (1:3)	Sqm	116.85	Rupees One Hundred Sixteen And Paise Eighty Five Only
2	1366.36	Earthwork in execavation for foundation of structure like culverts, retaining wall etc., as per drawing and technical specification, including setting out, construction of shoring and bracing, dressing of sides and bottom, back filling with approved material, disposal of balance earth as per specification, including cost of labour, HOM etc., complete. In all kinds of soil by manual means.	Cum	273.60	Rupees Two Hundred Seventy Three And Paise Sixty Only
3	2372.70	Providing granite slabs of selected quality roughly dressed having a size of 7.5 cms thick and fixed in cement mortar (1:6)	Sqm	779.03	Rupees Seven Hundred Seventy Nine And Paise Three Only
4	21.73	KSRRB M2100-10. Providing and laying Plain cement concrete of mix 1:3:6 with OPC @ 220kgs, with crushed 40mm and down size graded granite metal coarse aggregates @0.89cum and fine aggregates @ 0.46cum, in foundation mechanically mixed, placed in foundation and compacted by vibration including curing for 14 days including cost of all materials, labour, HOM curing, form works, scaffolding and centering complete as per specifications.	Cum	5692.45	Rupees Five Thousand Six Hundred Ninety Two And Paise Forty Five Only
5	48.89	KSRB 5.2-3 : Providing and constructing granite / trap / basalt size stone masonry in foundation with cement mortar, stone hammered dressed in courses not less than 20 cms high, bond stones at 2m. apart in each course including cost of materials, labour, curing complete as per specifications.	Cum	5114.86	Rupees Five Thousand One Hundred Fourteen And Paise Eighty Six Only
6	447.67	KSRB 4-1.6 ; Providing and laying in position plain cement concrete of Mix 1:2:4 with OPC @ 240kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.878 cum and fine aggregtes @ 0.53cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM curing complete as per specifications.	Cum	6034.11	Rupees Six Thousand Thirty Four And Paise Eleven Only
7	1626.04	KSRB 5-14 : Providing and constructing load bearing wall with solid concrete blocks of size 400x150x200 mm having block density not lessthan 1800 kg/m3 and having a minimum average compressive strength 4.00 N/mm2 confirming to IS 2185 (Part) : 2005 and constructed with CM 1:4 , as per IS 2572:2005 including cost of all materials, labour charegs, scaffolding, curing complete as per specifications	Sqm	1028.31	Rupees One Thousand Twenty Eight And Paise Thirty One Only

Contractor

Executive Engineer
Project Division
Yelahanka Zone
BBMP, Bangalore-92

Scanned by TapScanner

SNo	Quantity	Item Name	Unit	In figures	In words
8	3434.67	Providing and fixing RCC Precast cover slab of 100mm thick for drain in cement concrete M20 using graded granite jelly 20mm and down size with steel reinforcement, including form work, lift charges, curing and concrete finished surfaces on both sides etc, complete and as per drawing and the directions of Engineer in-charge.	Sqm	2453.62	Rupees Two Thousand Four Hundred Fifty Three And Paise Sixty Two Only
9	81.48	Providing and Fixing pre cast covering Slab 250mm thick made out of CC 1:2:4 and jelly 20mm Down size with steel reinforcement including form work,curing,including cost of alll materials, labour,hire charges of machinery, loading, unloading, lead and lift,transportation etc ,complete.As per Engineer incharge.	Sqm	5688.36	Rupees Five Thousand Six Hundred Eighty Eight And Paise Thirty Six Only
10	4778.00	Providing and fixing pre cast solid cement concrete kerb stones made out of CC 1:2:4 with top and bottom width 114 and 165 mm respectively, 400mm high and 450mm in length finished with CM 1:3 plastering and finishing cutting including formwork, curing, including cost of materials, labour charges of machinery, loading and unloading, lead and lift, transportation ete.,complete	Nos	454.06	Rupees Four Hundred Fifty Four And Paise Six Only

Executive Engineer
Project Division
Yelahanka Zone
BBMP, Bangalore-92

Contractor

Executive Engineer
Project Division
Yelahanka Zone

Scanned by TapScanner